

ADDENDUM 2

Peoria Park District
Planning, Design and Construction Department
1314 N. Park Road
Peoria, IL 61604
Telephone: (309) 686-3386

ADDENDUM NO. 2

PROJECT TITLE: AVIARY CURTAIN WALL
REPLACEMENT

ISSUANCE DATE: September 8, 2017

LOCATION: Peoria Zoo

The proposed Contract Documents for this Work are modified as follows:

I. **GENERAL:**

- A. To clarify, the temporary enclosure wall shall be of the following construction as a minimum. The exterior wall shall be wood/metal studs with plywood/osb on the exterior and covered with building wrap with taped joints/seams. Any roof construction shall be covered with peel and stick ice/water shield. The stud cavities shall be filled with kraft faced batt insulation, and drywall on the interior face of the studs. The interior enclosure wall shall be wood/metal studs with visqueen and plywood on the public side. The exterior door (if needed) shall be a standard hollow metal door and frame with threshold, weatherstripping, and deadbolt. An interior door shall be provided for Zoo and contractor access and can be the same as the exterior, or a plywood door with padlock may be substituted. The plywood door must be dust tight. Heights of temporary enclosures will be left up to the contractor, but the building must be kept secure and weathertight.

II. **DRAWINGS:**

N/A

III. **PROJECT MANUAL/SPECIFICATIONS/GENERAL CONDITIONS/ETC.:**

N/A

IV. **INVITATION TO BID:**

N/A

END OF ADDENDUM NO. 2

(Addendum may be bound into Project Manual, attached to front cover, faxed, mailed or delivered to bidders.)